



# Protected underground

Option	Basic	Standard	Lux
<b>Concrete</b>			
Square vertical extension (4509 kg)	x	x	x
Square entrance (10 430 kg)	x	x	x
End-cap with security door (3917 kg)	x	x	x
Standard module (13 755 kg)	x	x	x
End-cap with escape hatch (3917 kg)	x	x	x
Escape-shaft (5336 kg)	x	x	x
<b>Interior</b>			
Spiral staircase hot-dip galvanized	x	x	x
Exit ladder hot-dip galvanized	x	x	x
<b>Furniture</b>			x
Bunk bed			
Sink cabinet			
Sofa frame			
Wardrobe cabinet			
Shelves			
Table			
Mirror 55cm			
Stainless steel sink and faucet			
Dry toilet			
<b>Interior finishing</b>			
Floor LVT or tile		x	x
SBS waterproofing	x	x	x
Lime cement render / paint		x	x
Transportation costs for materials		x	x
<b>Blastproof equipment</b>			
Entrance hatch	x	x	x
Emergency hatch	x	x	x
Blastproof door 900 x 2000	x	x	x
Emergency exit door 600 x 800	x	x	x
Emergency exit insulation		x	x
Ventilation device VA-40		x	x
Ventilation device feedthrough		x	x
Ventilation chimney + parts		x	x
Overpressure valve		x	x
Relief valve grommet		x	x
Overpressure sensor + grommet		x	x
Co2 sensor		x	x
Normal time vent feed-through + closing mechanism	x	x	x
Water and electricity lead-in		x	x
<b>Electrical works</b>			
Materials			x
Labour			x
Battery system			x
Project management by project	x	x	x
<b>TOTAL (€)</b>	<b>46 905</b>	<b>58 880</b>	<b>69 595</b>

NB! PRICE DOES NOT INCLUDE: LANDSCAPING, TRANSPORTATION, INSTALLATION, HEATING, PUR FOAM\*

\*PUR FOAM IS NOT NECESSARY AS THE SHELTER IS DEEP UNDERGROUND, BUT ITS "NICE TO HAVE"