



Option	Basic	Standard	Lux
Concrete			
Square vertical extension (4509 kg)	x	x	x
Square entrance (10 430 kg)	x	x	x
End-cap with security door (3917 kg)	x	x	x
Standard module (13 755 kg)	x	x	x
End-cap with escape hatch (3917 kg)	x	x	x
Escape-shaft (5336 kg)	x	x	x
Interior			
Spiral staircase hot-dip galvanized	x	x	x
Exit ladder hot-dip galvanized	x	x	x
Furniture			x
Bunk bed			
Sink cabinet			
Sofa frame			
Wardrobe cabinet			
Shelves			
Table			
Mirror 55cm			
Stainless steel sink and faucet			
Dry toilet			
Interior finishing			
Floor LVT or tile		x	x
SBS waterproofing	x	x	x
Lime cement render / paint		x	x
Transportation costs for materials		x	x
Blastproof equipment			
Entrance hatch	x	x	x
Emergency hatch	x	x	x
Blastproof door 900 x 2000	x	x	x
Emergency exit door 600 x 800	x	x	x
Emergency exit insulation		x	x
Ventilation device		x	x
Ventilation device feedthrough		x	x
Ventilation chimney + parts		x	x
Overpressure valve		x	x
Relief valve grommet		x	x
Overpressure sensor + grommet		x	x
Co2 sensor		x	x
Normal time vent feed-through + closing mechanism	x	x	x
Water and electricity lead-in		x	x
Electrical works			
Materials		x	x
Labour		x	x
Battery system			x
Project management by project	x	x	x
TOTAL (€)	52 555	68 865	77 440
NB! PRICE DOES NOT INCLUDE: VAT, LANDSCAPING, TRANSPORTATION, INSTALLATION, HEATING, PUR FOAM*			
*PUR FOAM IS NOT NECESSARY AS THE SHELTER IS DEEP UNDERGROUND, BUT ITS NICE TO HAVE			